

FRENCH ROCKS DIVISION.

The 26th February 1898.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, French Rocks division, up to 19th March 1898, for restoring Guttal Tank, registered No. 142, Mandya taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 31st March 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at French Rocks between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer, and be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for restoring Guttal Tank", in default of which tenders will be rejected.

5. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Description of work.		Unit of work.	Rate per unit.
Bund—			
Earthwork to bund	C. yds.	8.919
New stone work	"	3.183
Old stone work	"	1.980
Backing with fresh jelly	"	990
B. M. stones	Each.	2
Grade stones new with bed slabs	"	1
Do old removing and re-fixing..	"	60
New bed slabs to the old grade stones $2 \times 1\frac{1}{2} \times \frac{1}{3}$	"	60
Tank No. stone	"	1
Date stone	"	1
Gauge stone	"	1
Jungle clearing	" Lump sum.	
Turfing front and rear slopes of bund	Sqr.	643.67
Sluice No. 1—			
<i>Sluices.</i>			
Excavation gravelly soil	C. yds.	10
Brick in surki mortar	C. ft.	505
Plastering do	Sqr.	4.02
Brick in surki mortar arch work	C. ft.	30
Burnt stone slabs	"	6
Dismantling the old rear cistern	" Lump sum.	
Sluice No. 2—			
Brick in surki mortar	C. ft.	140
Plastering do	Sqr.	1.86
Left waste weir—			
Excavation	C. yds.	62
Brick in surki mortar	C. ft.	1,585
Burnt stone slabs	"	101
Plastering with surki mortar	Sqr.	6.20
Jelly wedging to old apron	C. yds.	5
Rough stone work	"	11
Dismantling	C. ft.	120
Right waste weir—			
Excavation	C. yds.	89
Brick in surki mortar	C. ft.	742
Burnt stone slabs	"	161
Plastering with surki mortar	Sqr.	4.44
Rough stone work new	C. yds.	64
Wedging the old apron with jelly	"	10
Dismantling	C. ft.	111
Distribution—			
Silt clearing and widening channel	C. yds.	4,180
Fixing old bed grade stones	" Lump sum.	
Mile and zero stones	Each.	2
$\frac{1}{2}$ furlong or tank grade stones	"	15
Repairing the head sluice	" Lump sum.	
Do the old three waste weirs of one channel	Do	
Baling water	Do	

The 26th February 1898.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, French Rocks division, up to 19th March 1898, for restoring the Kirgaval Doddakere, registered No. 120, in Malvalli taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1899.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at French Rocks between the hours of 8 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer, and be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for restoring the Kirgaval Doddakere, registered No. 120, Malvalli taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Description of work.				Unit of work.	Rate per unit.
Bund—					
Earthwork to bund	C. yds.	52,930
New stone work	"	5,249
Old stone work	"	2,327
B. M. stones	Each.	2
Removing and re-fixing old grade stones with new bed slabs	"	40
Grade stones, new, complete	"	16
Tank Registered No. stone	"	1
Date stone	"	1
Gauge stone	"	1
Turfing front and rear slopes	Sqr.	2,153.21
Waste weir, left 140 feet long—					
Excavating foundations	C. yds.	211
Brick in surki mortar	C. ft.	6,355
Burnt stone slabs dressed	"	296
Plastering with surki mortar	Sqr.	15.45
New stone work	C. yd.	38
Old stone work	"	610
Baling water	Lump sum.	
Waste weir, right, 44 ft. long—					
Excavating foundations	C. yd.	67
Brick in surki mortar	C. ft.	1,367
Burnt stone slabs dressed	"	87
Plastering with surki mortar	Sqr.	2.6
Dismantling brick work	C. ft.	44
New stone work	C. yds.	19
Old stone work	"	98
Baling water	Lump sum.	
Sluices—Left sluice, new—					
Excavation in hard soil, re-filling the bund with the excavated earth including ramming	C. yds.	194
Brick in surki mortar	C. ft.	1,492
Burnt stone slabs dressed	"	110
Cut stone work neatly dressed	"	10
Plastering with surki mortar	Sqr.	4.04
Baling water	Lump sum.	
Rough stone work new	C. yds.	13
Right sluice—					
Excavating and raising rear cistern	Lump sum.	
Distribution—Left sluice channel—					
Excavating channel	C. yds.	2,396
Constructing an aqueduct across the left Kodihalla of the Kirgaval Doddakere tank	Lump sum.	
Constructing two silt dams	Do	

Description of work.	Unit of work.	Rate per unit.
Mile and zero stones	Each.	2
Bed grade stones	"	21
3 furlong or bund grade stones.. ..	"	2
Clearing jungle	Lump sum.	
Right sluice channel—		
Improving the channel for one mile	Lump sum.	
Mile and zero stones	Each.	2
Bed grade stones	"	16
1 furlong or bund grade stones	"	15
Constructing a silt dam	Lump sum.	
Clearing jungle	Do	

D. SITARAMA RAO, *Executive Engineer.*

BANGALORE CITY MUNICIPALITY.

COLLECTION DEPARTMENT.

The 31st December 1897.

The Office of the Collector of Municipal Taxes, City Municipality, is removed to the Head Office, Fort, where all official business connected with Municipal taxes, assessments, &c., is attended to daily, Sundays excepted.

Notice, dated 21st March 1898.

The following business will be transacted at an Ordinary Meeting of the Municipal Commissioners for the City of Bangalore to be held at their office premises at 7-30 A. M. on Thursday the 31st March 1898.

1. Cash Account Current, Mortuary Return, Itinerant Medical Officer's Return, Demand, Collection and Balance Statement, Progress Report of Works, Memo of Visitors to the Srinivasa Mandiram Library, City Municipal English and Kanarese Schools' Returns, Return of Cases attended by Midwives, Abstract of Lighting Reports, Maternity Return, Langarkhana Return, Statement of Materials, and Statement of Rewards for the destruction of dogs, &c., for February 1898.
2. Consideration of the desirability or otherwise of the continuance of the appointment of Octroi Manager.
3. Letter, dated 3rd March 1898, from Mr. Aga Abdulla Saib, Municipal Commissioner, No. I, Palace Division, proposing that early steps may be taken to procure Dr. Haffkine's "Serum."
4. Letter No. 6788, dated 9th March 1898, from the President, Municipal Commission, C. & M. Station, furnishing detailed information on the practice obtaining in that station with regard to the issue of licenses to dealers in cocoanuts.
5. Proposal to place a sum of Rs. 10,000 out of the general balance at the disposal of the President, to meet the expenditure connected with Plague Prevention Measures.
6. Draft budget estimates of receipts and disbursements for the year 1898-99.
7. Application from P. C. Arlappa Pille, Clerk and Record-keeper, praying for increase of pay.
8. Accounts connected with the last City Annual Market Show.
9. Government Proceedings No. 11301-3—L. F. 89-97, dated 14th March 1898, granting a loan of Rs. 50,000 on the usual terms to enable the Board to carry out special sanitary improvements.
10. Docket No. 11876—L. F. 92-97, dated 21st March 1898, from the Secretary to the Government, General and Revenue Departments, forwarding copy of communication from the Chief Engineer, *in re* the drainage scheme of the city.
11. Docket No. 2350, dated 24th January 1898, from the Senior Surgeon and Sanitary Commissioner with the Government of Mysore, forwarding a letter from Mr. Muhammad Usman, L. M. S., Sanitary Inspector, regarding allowances.
12. Proposal by the President to entertain two Lighting Inspectors on Rs. 15 each, instead of only one on Rs. 10 as at present.
13. Correspondence from the Plague Commissioner and Senior Surgeon and Sanitary Commissioner, regarding the desirability of introducing the supervision system into the City of Bangalore *re* Plague Prevention Measures.